

**Appendix I**  
**Construction – Conformity Analysis**

Alternative 2

<b>Staten Island Breakwaters Construction Activity</b>					
<b>Annual Emissions (ton/yr)</b>					
<b>Year</b>	<b>PM2.5</b>	<b>PM10</b>	<b>NOx</b>	<b>VOC</b>	<b>CO</b>
2018	0.0	0.0	0.0	0.0	0.0
2019	1.7	1.8	36.3	1.5	4.9
2020	3.1	3.3	66.2	3.0	12.7
2021+	<0.1	<0.1	0.1	<0.1	0.2

Staten Island Breakwaters Non-Road Emissions Factors

Equipment Lookup	Equipment Type	Equipment Code	Details	Engine type	Size (hp)	PM2.5	PM10	NOx	VOC	CO	SO2
AC_10	Air Compresso	AC		Diesel	10	0.150	0.154	1.860	0.241	1.930	0.002
BD_250	Bulldozer	BD		Diesel	250	0.016	0.017	0.614	0.086	0.191	0.002
CC_650	ge Crawler Cr	CC	) T Crane on Ba	Diesel	650	0.013	0.013	0.995	0.071	0.363	0.002
EX_330	Excavator	EX		Diesel	350	0.015	0.016	0.832	0.086	0.331	0.002
FEL_200	ont End Load	FEL		Diesel	200	0.017	0.018	0.807	0.093	0.270	0.002
FEL_300	ont End Load	FEL		Diesel	300	0.017	0.018	0.807	0.093	0.270	0.002
GEN_100	Generator	GEN		Diesel	100	0.029	0.030	1.600	0.179	0.884	0.002
DRI_450	Drill Rig	DRI		Diesel	450	0.018	0.018	1.550	0.106	0.454	0.002
CRA_200	Mobile Crane	CRA		Diesel	200	0.010	0.010	0.615	0.068	0.136	0.002
ASP_80	phalt Laying E	ASP		Diesel	80	0.042	0.043	1.300	0.132	1.210	0.003
ROL_80	Roller	ROL		Diesel	80	0.039	0.040	1.040	0.109	1.020	0.003
GEN_100	Generator	GEN		Diesel	100	0.029	0.030	1.600	0.179	0.884	0.002
TB_650	Tug Boat	TB	40' Tug Boat	Diesel	650	0.492	0.537	9.843	0.373	0.820	0.005
TB_1200	Tug Boat	TB	40' Tug Boat	Diesel	1200	0.492	0.537	9.843	0.373	0.820	0.005
TBG_120	Tug Boat	TBG	40' Tug Boat	Diesel	120	0.166	0.179	7.457	0.201	1.268	0.005

	PM2.5	PM10	NOx	VOC	CO	SO2
Tug Boat Emis: Main Engines g/hp-hr	0.49	0.54	9.84	0.37	0.82	0.01
Aux Generator g/hp-hr	0.17	0.18	7.46	0.20	1.27	0.01
g/hr	610.46	665.76	12706.73	471.58	1136.45	6.64

Equipment Code	Size (hp)	Data					
		Max of PM2.5	Max of PM10	Max of NOx	Max of VOC	Max of CO	Max of SO2
AC	10	0.150	0.154	1.860	0.241	1.930	0.002
CC	650	0.013	0.013	0.995	0.071	0.363	0.002
TB	1200	0.492	0.537	9.843	0.373	0.820	0.005
	650	0.492	0.537	9.843	0.373	0.820	0.005
EX	350	0.015	0.016	0.832	0.086	0.331	0.002
	200	0.017	0.018	0.807	0.093	0.270	0.002
FEL	300	0.017	0.018	0.807	0.093	0.270	0.002
	100	0.029	0.030	1.600	0.179	0.884	0.002
TBG	120	0.166	0.179	7.457	0.201	1.268	0.005
BD	250	0.016	0.017	0.614	0.086	0.191	0.002
DRI	450	0.018	0.018	1.550	0.106	0.454	0.002
CRA	200	0.010	0.010	0.615	0.068	0.136	0.002
ASP	80	0.042	0.043	1.300	0.132	1.210	0.003
ROL	80	0.039	0.040	1.040	0.109	1.020	0.003

Year	Sum of CO	Sum of VOC	Sum of NOx	Sum of PM10	Sum of PM2.5
2018	0.000	0.000	0.000	0.000	0.000
2019	1.923	0.549	10.663	0.453	0.419
2020	2.878	0.805	12.032	0.450	0.419
<b>Grand Total</b>	<b>4.800</b>	<b>1.355</b>	<b>22.695</b>	<b>0.904</b>	<b>0.837</b>

single=	7 am to 3 pm
extended=	7 am to 6 pm
double =	7 am to 1 pm
	Hours
single	8
extended	10
double	16

**Staten Island Breakwaters - Anticipated Construction Schedule & Equipment Emissions**

Phase	Work task	Location	Start Date	End Date	Shift	Equipment Type	Equipment Code	Details	Engine type	Size (hp)	Quantity	Peak Daily Use	Average Use for Duration	Elevation and other Notes	Expected Annual Energy Use (hp-hr)	Emission Rates (g/hp-hr)					Emissions (ton)					Year
																PM2.5	PM10	NOx	VOC	CO	PM2.5	PM10	NOx	VOC	CO	
1a	Shoreline Construction	Project Site	10/1/2019	12/31/2019	single	Excavator	EX	Excavator	Diesel	350	2	100%	100%		369600	0.015	0.016	0.832	0.086	0.331	0.006	0.006	0.339	0.035	0.135	2019
	Shoreline Construction	Project Site	10/1/2019	12/31/2019	single	Front End Loaders	FEL	Front End Loaders	Diesel	200	2	100%	100%		211200	0.017	0.018	0.807	0.093	0.270	0.004	0.004	0.188	0.022	0.063	2019
	Shoreline Construction	Project Site	10/1/2019	12/31/2019	single	Generator	GEN	Generator	Diesel	100	1	100%	100%		52800	0.029	0.030	1.600	0.179	0.884	0.002	0.002	0.093	0.010	0.051	2019
	Shoreline Construction	Project Site	10/1/2019	12/31/2019	single	Compressor	AC	Compressor	Diesel	10	1	100%	100%		5280	0.150	0.154	1.860	0.241	1.930	0.001	0.001	0.011	0.001	0.011	2019
1b	Shoreline Construction	Project Site	1/1/2020	12/31/2020	single	Excavator	EX	Excavator	Diesel	350	2	100%	100%		1467200	0.015	0.016	0.832	0.086	0.331	0.024	0.025	1.346	0.139	0.535	2020
	Shoreline Construction	Project Site	1/1/2019	12/31/2020	single	Front End Loaders	FEL	Front End Loaders	Diesel	200	2	100%	100%		1673600	0.017	0.018	0.807	0.093	0.270	0.032	0.033	1.489	0.172	0.498	2020
	Shoreline Construction	Project Site	1/1/2019	12/31/2020	single	Generator	GEN	Generator	Diesel	100	1	100%	100%		418400	0.029	0.030	1.600	0.179	0.884	0.013	0.014	0.738	0.083	0.408	2020
	Shoreline Construction	Project Site	1/1/2019	12/31/2020	single	Compressor	AC	Compressor	Diesel	10	1	100%	100%		41840	0.150	0.154	1.860	0.241	1.930	0.007	0.007	0.086	0.011	0.089	2020
2a	Breakwaters Construction	Project Site	6/1/2019	11/30/2019	extended	Crane	CC	Crane Barge	Diesel	650	1	100%	100%		845000	0.013	0.013	0.995	0.071	0.363	0.012	0.012	0.927	0.066	0.338	2019
	Breakwaters Construction	Project Site	6/1/2019	11/30/2019	extended	On-Site Crew Boat	TB	Crew Boat	Diesel	650	1	33%	100%		275357	0.492	0.537	9.843	0.373	0.820	0.149	0.163	2.988	0.113	0.249	2019
	Breakwaters Construction	Project Site	6/1/2019	11/30/2019	extended	On-Site Tugboat	TB	Tugboat-Engine	Diesel	1200	1	25%	100%		390000	0.492	0.537	9.843	0.373	0.820	0.212	0.231	4.232	0.160	0.353	2019
	Breakwaters Construction	Project Site	6/1/2019	11/30/2019	extended	On-Site Tugboat	TBG	Tugboat-Generator	Diesel	120	1	25%	100%		39000	0.166	0.179	7.457	0.201	1.268	0.007	0.008	0.321	0.009	0.054	2019
	Breakwaters Construction	Project Site	6/1/2019	11/30/2019	extended	Transport Barge Tgboat	TB	Tugboat-Engine	Diesel	1200	1	0%	0%		0	0.492	0.537	9.843	0.373	0.820	0.000	0.000	0.000	0.000	0.000	2019
	Breakwaters Construction	Project Site	6/1/2019	11/30/2019	extended	Transport Barge Tgboat	TBG	Tugboat-Generator	Diesel	120	1	0%	0%		0	0.166	0.179	7.457	0.201	1.268	0.000	0.000	0.000	0.000	0.000	2019
2b	Breakwaters Construction	Project Site	6/1/2020	10/31/2020	extended	Crane	CC	Crane Barge	Diesel	650	1	100%	100%		715000	0.013	0.013	0.995	0.071	0.363	0.010	0.010	0.784	0.056	0.286	2020
	Breakwaters Construction	Project Site	6/1/2020	10/31/2020	extended	On-Site Crew Boat	TB	Crew Boat	Diesel	650	1	33%	100%		232995	0.492	0.537	9.843	0.373	0.820	0.126	0.138	2.528	0.096	0.211	2020
	Breakwaters Construction	Project Site	6/1/2020	10/31/2020	extended	On-Site Tugboat	TB	Tugboat-Engine	Diesel	1200	1	25%	100%		330000	0.492	0.537	9.843	0.373	0.820	0.179	0.195	3.581	0.136	0.298	2020
	Breakwaters Construction	Project Site	6/1/2020	10/31/2020	extended	On-Site Tugboat	TBG	Tugboat-Generator	Diesel	120	1	25%	100%		33000	0.166	0.179	7.457	0.201	1.268	0.006	0.007	0.271	0.007	0.046	2020
	Breakwaters Construction	Project Site	6/1/2020	10/31/2020	extended	Transport Barge Tgboat	TB	Tugboat-Engine	Diesel	1200	1	0%	0%		0	0.492	0.537	9.843	0.373	0.820	0.000	0.000	0.000	0.000	0.000	2020
	Breakwaters Construction	Project Site	6/1/2020	10/31/2020	extended	Transport Barge Tgboat	TBG	Tugboat-Generator	Diesel	120	1	0%	0%		0	0.166	0.179	7.457	0.201	1.268	0.000	0.000	0.000	0.000	0.000	2020
3a	Water Hub	Project Site	6/1/2019	12/31/2019	single	Drill Rig	DRI	Drill Rig	Diesel	450	1	100%	100%		547200	0.018	0.018	1.550	0.106	0.454	0.011	0.011	0.935	0.064	0.274	2019
	Water Hub	Project Site	6/1/2019	12/31/2019	single	Mobile Crane	CRA	Mobile Crane	Diesel	200	1	100%	100%		243200	0.010	0.010	0.615	0.068	0.136	0.003	0.003	0.165	0.018	0.036	2019
	Water Hub	Project Site	6/1/2019	12/31/2019	single	Asphalt Laying Eqp	ASP	Asphalt Laying Eqp	Diesel	80	1	100%	100%		97280	0.042	0.043	1.300	0.132	1.210	0.004	0.005	0.139	0.014	0.130	2019
	Water Hub	Project Site	6/1/2019	12/31/2019	single	Roller	ROL	Roller	Diesel	80	1	100%	100%		97280	0.039	0.040	1.040	0.109	1.020	0.004	0.004	0.112	0.012	0.109	2019
	Water Hub	Project Site	6/1/2019	12/31/2019	single	Generator	GEN	Generator	Diesel	100	1	100%	100%		121600	0.029	0.030	1.600	0.179	0.884	0.004	0.004	0.214	0.024	0.118	2019
	Water Hub	Project Site	1/1/2020	5/31/2020	single	Drill Rig	DRI	Drill Rig	Diesel	450	1	100%	100%		388800	0.018	0.018	1.550	0.106	0.454	0.008	0.008	0.664	0.045	0.195	2020
3b	Water Hub	Project Site	1/1/2020	5/31/2020	single	Mobile Crane	CRA	Mobile Crane	Diesel	200	1	100%	100%		172800	0.010	0.010	0.615	0.068	0.136	0.002	0.002	0.117	0.013	0.026	2020
	Water Hub	Project Site	1/1/2020	5/31/2020	single	Asphalt Laying Eqp	ASP	Asphalt Laying Eqp	Diesel	80	1	100%	100%		69120	0.042	0.043	1.300	0.132	1.210	0.003	0.003	0.099	0.010	0.092	2020
	Water Hub	Project Site	1/1/2020	5/31/2020	single	Roller	ROL	Roller	Diesel	80	1	100%	100%		69120	0.039	0.040	1.040	0.109	1.020	0.003	0.003	0.079	0.008	0.078	2020
	Water Hub	Project Site	1/1/2020	5/31/2020	single	Generator	GEN	Generator	Diesel	100	1	100%	100%		86400	0.029	0.030	1.600	0.179	0.884	0.003	0.003	0.152	0.017	0.084	2020
			Project Site	1/1/2018	1/1/2018											0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	2018		
	4	Beach Fill	Project Site	6/17/2020	7/26/2020	single	Bulldozer	BD	Bulldozer	Diesel	250	1	100%	100%		56000	0.016	0.017	0.614	0.086	0.191	0.001	0.001	0.038	0.005	0.012
Beach Fill		Project Site	6/17/2020	7/26/2020	single	Front End Loader	FEL	Front End Loader	Diesel	300	1	100%	100%		67200	0.017	0.018	0.807	0.093	0.270	0.001	0.001	0.060	0.007	0.020	2020

Crew Boat Distance 3 mi  
Average Speed 6.4 knots  
RT Time 0.81 hr  
49 min

Data						
Year	Sum of PM2.5	Sum of PM10	Sum of NOx	Sum of VOC	Sum of CO	
2018	0.000		0.000	0.000	0.000	0.000
2019	0.089		0.097	1.808	0.079	0.439
2020	0.794		0.863	16.087	0.699	3.910
<b>Grand Total</b>	<b>0.883</b>		<b>0.959</b>	<b>17.895</b>	<b>0.777</b>	<b>4.349</b>

**Staten Island Breakwaters - Truck Cruise Emissions**

#	Work task	Stage	Location	Start Date	End Date	# of Workers per day	Monthly Worker Trips	# of Workers	Average		Round Trip		Emission Rates (g/m)					Emissions (ton)					Year
									Speed (mph)	Travel Time (hr)	Distance (mi)	VMT	PM2.5	PM10	NOx	VOC	CO	PM2.5	PM10	NOx	VOC	CO	
1	Shoreline Project	Earthen Berm	Project Site	10/1/2019	12/31/2019	15		836	25	1.0112	25.28	21134.1	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.01	0.00	0.06	2019
	Shoreline Project		Project Site	1/1/2020	1/31/2020	15		291	25	1.0112	25.28	7356.48	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.00	0.00	0.02	2020
	Shoreline Project	Eco-Retvetment (between Brighton Street and Manhattan Street)	Project Site	12/1/2019	12/31/2019	15		279	25	1.0112	25.28	7053.12	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.00	0.00	0.02	2019
	Shoreline Project		Project Site	1/1/2020	2/29/2020	15		544	25	1.0112	25.28	13752.3	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.00	0.00	0.04	2020
	Shoreline Project	Hybrid Dune/Retvetment	Project Site	2/1/2020	6/30/2020	15		1355	25	1.0112	25.28	34254.4	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.01	0.00	0.10	2020
	Shoreline Project	Eco-Retvetment (between Loretto Street and Sprague Avenue)	Project Site	6/1/2020	8/31/2020	15		836	25	1.0112	25.28	21134.1	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.01	0.00	0.06	2020
	Shoreline Project	Raised Edge (Retvetment with Trail)	Project Site	7/1/2020	12/31/2020	15		1671	25	1.0112	25.28	42242.9	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.01	0.00	0.13	2020
	Shoreline Project	Transition Nodes	Project Site	6/1/2020	8/31/2020	15		836	25	1.0112	25.28	21134.1	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.01	0.00	0.06	2020
2	Breakwater Construction	Breakwater Construction	Project Site	6/1/2019	11/30/2019	11		1207	25	1.0112	25.28	30513	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.01	0.00	0.09	2019
	Breakwater Construction	Breakwater Construction	Project Site	6/1/2020	10/31/2020	11		1021	25	1.0112	25.28	25810.9	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.01	0.00	0.08	2020
3	Water Hub	Water Hub	Project Site	6/1/2019	12/31/2019	15		1924	25	1.0112	25.28	48638.7	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.01	0.00	0.15	2019
	Water Hub	Water Hub	Project Site	1/1/2020	5/31/2020	15		1367	25	1.0112	25.28	34557.8	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.01	0.00	0.11	2020
4	Beach Fill Delivery	Beach Fill Delivery	Project Site	7/1/2020	8/31/2020	6		223	25	1.0112	25.28	5637.44	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.00	0.00	0.02	2020

Emissions Rates for Auto Vehicles Traveling at 25 mph

Notes

Trucks assumed to travel at an average speed (including delays associated with congestion and red lights) of 25 mph  
Trucks origin/destination assumed to be within 1 hour travel time from project site

AVO 1.09  
Auto Share 92%

Trip Distance: 12.64

\*Source: From Transportation Energy Data Book - Edition 34, Table 8.9 (Trip Statistics by Trip Purpose)  
X:\DEPARTMENTS\Air Quality\Resources\Energy\Transportation Energy Data Book (ORNL)

Year	Data					
	Sum of PM2.5	Sum of PM10	Sum of NOx	Sum of VOC	Sum of CO	
2018	0.000		0.000	0.000	0.000	0.000
2019	0.089		0.097	1.808	0.079	0.439
2020	0.794		0.863	16.087	0.699	3.910
Grand Total	0.883		0.959	17.895	0.777	4.349

**Staten Island Breakwaters - Truck Cruise Emissions**

#	Work task	Stage	Location	Start Date	End Date	Truck Type	Truck Code	Daily Trucks	Total Deliveries for Period	Average Speed (mph)	Travel Time (hr)	Round Trip Distance		Emission Rates (g/mi)					Emissions (ton)					Year	
												Distance (mi)	VMT	PM2.5	PM10	NOx	VOC	CO	PM2.5	PM10	NOx	VOC	CO		
1	Shoreline Project	Earthen Berm	Project Site	10/1/2019	12/31/2019	Dump Truck	DT	3	198	25	7.344	184	36352.8	0.56	0.61	11.30	0.49	2.75	0.02	0.02	0.45	0.02	0.11	2019	
	Shoreline Project		Project Site	1/1/2020	1/31/2020	Dump Truck	DT	3	69	25	7.344	184	12668.4	0.56	0.61	11.30	0.49	2.75	0.01	0.01	0.16	0.01	0.04	2020	
	Shoreline Project	Eco-Revetment (between Brighton Street and Manhattan Street)	Project Site	12/1/2019	12/31/2019	Dump Truck	DT	2	44	25	7.344	184	8078.4	0.56	0.61	11.30	0.49	2.75	0.00	0.01	0.10	0.00	0.02	2019	
	Shoreline Project		Project Site	1/1/2020	2/29/2020	Dump Truck	DT	2	86	25	7.344	184	15789.6	0.56	0.61	11.30	0.49	2.75	0.01	0.01	0.20	0.01	0.05	2020	
	Shoreline Project	Hybrid Dune/Revetment	Project Site	2/1/2020	6/30/2020	Dump Truck	DT	15	1605	25	7.344	184	294678	0.56	0.61	11.30	0.49	2.75	0.18	0.20	3.67	0.16	0.89	2020	
	Shoreline Project	Eco-Revetment (between Loretto Street and Sprague Avenue)	Project Site	6/1/2020	8/31/2020	Dump Truck	DT	7	462	25	7.344	184	84823.2	0.56	0.61	11.30	0.49	2.75	0.05	0.06	1.06	0.05	0.26	2020	
	Shoreline Project	Raised Edge (Revetment with Trail)	Project Site	7/1/2020	12/31/2020	Dump Truck	DT	19	2508	25	7.344	184	460469	0.56	0.61	11.30	0.49	2.75	0.28	0.31	5.74	0.25	1.39	2020	
	Shoreline Project	Transition Nodes	Project Site	6/1/2020	8/31/2020	Dump Truck	DT	3	198	25	7.344	184	36352.8	0.56	0.61	11.30	0.49	2.75	0.02	0.02	0.45	0.02	0.11	2020	
	2	Breakwater Construction	Breakwater Construction	Project Site	7/16/2018	1/31/2019				0	25	7.344	184	0	0.56	0.61	11.30	0.49	2.75	0.00	0.00	0.00	0.00	0.00	2018
	3	Water Hub	Water Hub	Project Site	6/1/2019	12/31/2019	Concrete Truck	CT	2.5	380	25	0.6	15	5700	0.56	0.61	11.30	0.49	2.75	0.00	0.00	0.07	0.00	0.02	2019
Water Hub		Water Hub	Project Site	1/1/2020	5/31/2020	Concrete Truck	CT	2.5	270	25	0.6	15	4050	0.56	0.61	11.30	0.49	2.75	0.00	0.00	0.05	0.00	0.01	2020	
Water Hub		Water Hub	Project Site	6/1/2019	12/31/2019	Tractor Trailer	TT	2.5	380	25	10	250	95000	0.56	0.61	11.30	0.49	2.75	0.06	0.06	1.18	0.05	0.29	2019	
4	Beach Fill Delivery	Beach Fill Delivery	Project Site	1/1/2020	5/31/2020	Tractor Trailer	TT	2.5	270	25	10	250	67500	0.56	0.61	11.30	0.49	2.75	0.04	0.05	0.84	0.04	0.20	2020	
			Project Site	7/1/2020	8/31/2020	Dump Truck	DT	39	1716	25	7.344	184	315058	0.56	0.61	11.30	0.49	2.75	0.19	0.21	3.92	0.17	0.95	2020	

Emissions Rates for Heavy Vehicles Traveling at 25 mph

Notes

- Trucks assumed to travel at an average speed (including delays associated with congestion and red lights) of 25 mph
- Trucks origin/destination assumed to be within 1 hour travel time from project site

Data					
Year	Sum of PM2.5	Sum of PM10	Sum of NOx	Sum of VOC	Sum of CO
2018	0.000	0.000	0.000	0.000	0.000
2019	0.002	0.002	0.026	0.003	0.007
2020	0.002	0.003	0.039	0.004	0.011
Grand Total	0.004	0.004	0.066	0.007	0.018

**Staten Island Breakwaters - Construction Truck Idle Emissions**

Phase	Work task	Location	Start Date	End Date	Truck Type	Truck Code	Total Deliveries for Period	On-Site Vehicle Idle Time (hr)	Total On-Site Idle Time (hr)	Emission Rates (g/hr)					Emissions (ton)					Year
										PM2.5	PM10	NOx	VOC	CO	PM2.5	PM10	NOx	VOC	CO	
1	Shoreline Project	Project Site	10/1/2019	12/31/2019	Dump Truck	DT	198	0.05	9.9	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2019
	Shoreline Project	Project Site	1/1/2020	1/31/2020	Dump Truck	DT	69	0.05	3.45	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2020
	Shoreline Project	Project Site	12/1/2019	12/31/2019	Dump Truck	DT	44	0.05	2.2	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2019
	Shoreline Project	Project Site	1/1/2020	2/29/2020	Dump Truck	DT	86	0.05	4.3	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2020
	Shoreline Project	Project Site	2/1/2020	6/30/2020	Dump Truck	DT	1605	0.05	80.25	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.01	0.00	0.00	2020
	Shoreline Project	Project Site	6/1/2020	8/31/2020	Dump Truck	DT	462	0.05	23.1	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2020
	Shoreline Project	Project Site	7/1/2020	12/31/2020	Dump Truck	DT	2508	0.05	125.4	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.01	0.00	0.00	2020
	Shoreline Project	Project Site	6/1/2020	8/31/2020	Dump Truck	DT	198	0.05	9.9	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2020
	2	Breakwater Construction	Project Site	7/16/2018	1/31/2019				0.05	0	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00
3	Water Hub	Project Site	6/1/2019	12/31/2019	Concrete Truck	CT	380	1	380	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.02	0.00	0.01	2019
	Water Hub	Project Site	1/1/2020	5/31/2020	Concrete Truck	CT	270	1	270	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.02	0.00	0.00	2020
	Water Hub	Project Site	6/1/2019	12/31/2019	Tracotr Trailer	TT	380	0.05	19	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2019
	Water Hub	Project Site	1/1/2020	5/31/2020	Tracotr Trailer	TT	270	0.05	13.5	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2020
4	Beach Fill Delivery	Project Site	7/1/2020	8/31/2020	Dump Truck	DT	1716	0.05	85.8	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.01	0.00	0.00	2020

Idle Emissions Rates for Heavy Vehicles

Notes

- Concrete Trucks are assumed to idle for 1 hour per trip on site
- Dump Truck / Flat Bed Truck are assumed to idle for 3 minutes per trip on site

Data						
Year	Sum of PM2.5	Sum of PM10	Sum of NOx	Sum of CO	Sum of VOC	
2019	1.051	1.146	21.871	1.956	0.812	
2020	1.051	1.146	21.871	1.956	0.812	
<b>Grand Total</b>	<b>2.101</b>	<b>2.292</b>	<b>43.742</b>	<b>3.912</b>	<b>1.623</b>	

**Staten Island Breakwaters - Tug Boat Delivery Emissions**

Phase	Work task	Location	Start Date	End Date	Truck Type	Truck Code	Total Deliveries for Period	Round Trip Distance (mi)	VMT	Average Speed (knots)	Travel Time (hr)	Emission Rates (g/hr)					Emissions (ton)					Year
												PM2.5	PM10	NOx	VOC	CO	PM2.5	PM10	NOx	VOC	CO	
2a	Breakwaters	Project Site	6/1/2019	11/30/2019	Tug Boat/Barge	TB	115	100	11500	6.4	1561.4	610.46	665.76	12706.73	471.58	1136.45	1.05	1.15	21.87	0.81	1.96	2019
2b	Breakwaters	Project Site	6/1/2020	10/31/2020	Tug Boat/Barge	TB	115	100	11500	6.4	1561.4	610.46	665.76	12706.73	471.58	1136.45	1.05	1.15	21.87	0.81	1.96	2020
							Total		230													

Notes

Tugs assumed to travel at an average speed of 6.4 knots  
Round Trip Distance measured between site and Tilcon Quarry Sheafe Road New Hamburg, NY 12590



Total Square Footage (gsf)
8,900

**Emission Factors (lb/MMBtu)**

	PM2.5	PM10	NOx	VOC	CO	SO2
Fuel Oil	0.0075	0.0075	0.0980	0.0054	0.0824	0.0006
Natural Gas	0.0121	0.0121	0.1286	0.0178	0.0357	0.0015

2005 Energy Consumption Factor for New York:

60.3	tho Btu/yr-sqft
------	-----------------

Heating Values

Fuel Oil	140,000	Btu/gal
Natural Gas	1,020	Btu/scf

Sulfur Content	15	ppm
----------------	----	-----

	Annual Consumption	
Energy	537	MMBtu/yr
Fuel Oil	3,833	gal/yr
Natural Gas	52,615	scf/yr

**Emission (lb/yr)**

	PM2.5	PM10	NOx	VOC	CO	SO2
Fuel Oil	4.0	4.0	52.6	2.9	44.2	0.3
Natural Gas	6.5	6.5	69.0	9.6	19.2	0.8

Proposed Event/Activity	Season/Month	Frequency	Approximate Attendance	Likely Travel Method
Tree planting events	Spring/Fall	Twice per year	100-300	Auto/bus
Beach cleanups with schools, Boy Scouts, and Girl Scouts	Throughout the year	Ideally three times per week and as scheduled	Groups of 10 to 50	Auto
First day of season beach walks	Spring, Summer, Fall, and Winter	Four times per year	5-25	Auto
Earth/Arbor Day activities	April	One day or week per year	25-100	Auto/Bus
DEC citizen science Horseshoe crab monitoring	May-June	Once a year	5-15	Auto
CHP Dunes, Drawing, and Dendrology "Walk and talk"	May-September	Once per month (Sunday)	5-25	Auto
CHP Dunes, Drawing, and Dendrology EarthART	May-September	Once per month (Wednesday)	5-25	Auto
CHP Dunes, Drawing, and Dendrology "Chalk and talk"	May-September	Once per month (weekday)	5-25	Auto
CHP Dunes, Drawing, and Dendrology "Coastal Crafting"	May-September	Once per week (Saturday)	5-25	Auto
Shore birding talks and walks	Spring and Fall	Four times per year	5-25	Auto
Exhibitions	Throughout the year	Shows generally run for 4-6 weeks	XX	Auto
Greenbelt Education extension (maritime focus)	July-August (summer camp and school field trips during the school year)		Summer Camp 20-25/Field Trips - 10-15	Auto/Bus

School Bus Occupancy	17
Auto Occupancy	1.75

CEQR Table 18-7 Average One-Way Taxi Trip Lengths (Miles)				
Origin	Manhattan	Manhattan	Other NYC	Unknown Destination
	2		9	2.32
		11	6	7.88
		2.32	7.88	N/A

Annual Attendance	Annual Vehicles	
	Autos	Bus
600	343	35
7800	4,457	
100	57	
700	400	41
15	9	
300	171	
300	171	
300	171	
300	171	
100	57	
3825		225
	6,009	301
	Annual VMT	
	47,348	2,376

Conservatively includes maximum attendance utilizing both auto and bus

Conservatively includes maximum attendance utilizing both auto and bus

9 weeks (5 days per week) summer camp; 180 school days; exclusively bus

	Emission Factors (g/mi)				
	PM2.5	PM10	NOx	VOC	CO
Auto	0.008	0.009	0.250	0.066	2.758
Bus	0.442	0.481	16.127	1.018	6.011

Emissions (ton)				
0.002	0.002	0.055	0.006	0.160

Alternative 3

<b>Staten Island Breakwaters Construction Activity</b>					
<b>Annual Emissions (ton/yr)</b>					
<b>Year</b>	<b>PM2.5</b>	<b>PM10</b>	<b>NOx</b>	<b>VOC</b>	<b>CO</b>
2018	0.0	0.0	0.0	0.0	0.0
2019	1.6	1.7	34.5	1.4	4.4
2020	1.9	2.0	39.9	1.6	5.7
2021+	<0.1	<0.1	0.1	<0.1	0.2

Staten Island Breakwaters Non-Road Emissions Factors

Equipment Lookup	Equipment Type	Equipment Code	Details	Engine type	Size (hp)	PM2.5	PM10	NOx	VOC	CO	SO2
AC_10	Air Compresso	AC		Diesel	10	0.150	0.154	1.860	0.241	1.930	0.002
BD_250	Bulldozer	BD		Diesel	250	0.016	0.017	0.614	0.086	0.191	0.002
CC_650	ge Crawler Cr	CC	) T Crane on Ba	Diesel	650	0.013	0.013	0.995	0.071	0.363	0.002
EX_330	Excavator	EX		Diesel	350	0.015	0.016	0.832	0.086	0.331	0.002
FEL_200	ont End Load	FEL		Diesel	200	0.017	0.018	0.807	0.093	0.270	0.002
FEL_300	ont End Load	FEL		Diesel	300	0.017	0.018	0.807	0.093	0.270	0.002
GEN_100	Generator	GEN		Diesel	100	0.029	0.030	1.600	0.179	0.884	0.002
DRI_450	Drill Rig	DRI		Diesel	450	0.018	0.018	1.550	0.106	0.454	0.002
CRA_200	Mobile Crane	CRA		Diesel	200	0.010	0.010	0.615	0.068	0.136	0.002
ASP_80	phalt Laying E	ASP		Diesel	80	0.042	0.043	1.300	0.132	1.210	0.003
ROL_80	Roller	ROL		Diesel	80	0.039	0.040	1.040	0.109	1.020	0.003
GEN_100	Generator	GEN		Diesel	100	0.029	0.030	1.600	0.179	0.884	0.002
TB_650	Tug Boat	TB	40' Tug Boat	Diesel	650	0.492	0.537	9.843	0.373	0.820	0.005
TB_1200	Tug Boat	TB	40' Tug Boat	Diesel	1200	0.492	0.537	9.843	0.373	0.820	0.005
TBG_120	Tug Boat	TBG	40' Tug Boat	Diesel	120	0.166	0.179	7.457	0.201	1.268	0.005

	PM2.5	PM10	NOx	VOC	CO	SO2
Tug Boat Emis: Main Engines g/hp-hr	0.49	0.54	9.84	0.37	0.82	0.01
Aux Generator g/hp-hr	0.17	0.18	7.46	0.20	1.27	0.01
g/hr	610.46	665.76	12706.73	471.58	1136.45	6.64

Equipment Code	Size (hp)	Data					
		Max of PM2.5	Max of PM10	Max of NOx	Max of VOC	Max of CO	Max of SO2
AC	10	0.150	0.154	1.860	0.241	1.930	0.002
CC	650	0.013	0.013	0.995	0.071	0.363	0.002
TB	1200	0.492	0.537	9.843	0.373	0.820	0.005
	650	0.492	0.537	9.843	0.373	0.820	0.005
EX	350	0.015	0.016	0.832	0.086	0.331	0.002
	200	0.017	0.018	0.807	0.093	0.270	0.002
FEL	300	0.017	0.018	0.807	0.093	0.270	0.002
	100	0.029	0.030	1.600	0.179	0.884	0.002
TBG	120	0.166	0.179	7.457	0.201	1.268	0.005
BD	250	0.016	0.017	0.614	0.086	0.191	0.002
DRI	450	0.018	0.018	1.550	0.106	0.454	0.002
CRA	200	0.010	0.010	0.615	0.068	0.136	0.002
ASP	80	0.042	0.043	1.300	0.132	1.210	0.003
ROL	80	0.039	0.040	1.040	0.109	1.020	0.003

Year	Sum of CO	Sum of VOC	Sum of NOx	Sum of PM10	Sum of PM2.5
2018	0.000	0.000	0.000	0.000	0.000
2019	1.662	0.481	10.032	0.440	0.406
2020	1.348	0.401	8.374	0.371	0.342
<b>Grand Total</b>	<b>3.010</b>	<b>0.881</b>	<b>18.406</b>	<b>0.812</b>	<b>0.748</b>

single=	7 am to 3 pm
extended=	7 am to 6 pm
double =	7 am to 11 pm
	Hours
single	8
extended	10
double	16

**Staten Island Breakwaters - Anticipated Construction Schedule & Equipment Emissions**

Phase	Work task	Location	Start Date	End Date	Shift	Equipment Type	Equipment Code	Details	Engine type	Size (hp)	Quantity	Peak Daily Use	Average Use for Duration	Elevation and other Notes	Expected Annual Energy Use (hp-hr)	Emission Rates (g/hp-hr)					Emissions (ton)					Year
																PM2.5	PM10	NOx	VOC	CO	PM2.5	PM10	NOx	VOC	CO	
1a	Shoreline Construction	Project Site	10/1/2019	12/31/2019	single	Excavator	EX	Excavator	Diesel	350	2	100%	100%			0.015	0.016	0.832	0.086	0.331	0.000	0.000	0.000	0.000	0.000	2019
	Shoreline Construction	Project Site	10/1/2019	12/31/2019	single	Front End Loaders	FEL	Front End Loaders	Diesel	200	2	100%	100%			0.017	0.018	0.807	0.093	0.270	0.000	0.000	0.000	0.000	0.000	2019
	Shoreline Construction	Project Site	10/1/2019	12/31/2019	single	Generator	GEN	Generator	Diesel	100	1	100%	100%			0.029	0.030	1.600	0.179	0.884	0.000	0.000	0.000	0.000	0.000	2019
	Shoreline Construction	Project Site	10/1/2019	12/31/2019	single	Compressor	AC	Compressor	Diesel	10	1	100%	100%			0.150	0.154	1.860	0.241	1.930	0.000	0.000	0.000	0.000	0.000	2019
1b	Shoreline Construction	Project Site	1/1/2020	12/31/2020	single	Excavator	EX	Excavator	Diesel	350	2	100%	100%			0.015	0.016	0.832	0.086	0.331	0.000	0.000	0.000	0.000	0.000	2020
	Shoreline Construction	Project Site	1/1/2019	12/31/2020	single	Front End Loaders	FEL	Front End Loaders	Diesel	200	2	100%	100%			0.017	0.018	0.807	0.093	0.270	0.000	0.000	0.000	0.000	0.000	2020
	Shoreline Construction	Project Site	1/1/2019	12/31/2020	single	Generator	GEN	Generator	Diesel	100	1	100%	100%			0.029	0.030	1.600	0.179	0.884	0.000	0.000	0.000	0.000	0.000	2020
	Shoreline Construction	Project Site	1/1/2019	12/31/2020	single	Compressor	AC	Compressor	Diesel	10	1	100%	100%			0.150	0.154	1.860	0.241	1.930	0.000	0.000	0.000	0.000	0.000	2020
2a	Breakwaters Construction	Project Site	6/1/2019	11/30/2019	extended	Crane	CC	Crane Barge	Diesel	650	1	100%	100%		845000	0.013	0.013	0.995	0.071	0.363	0.012	0.012	0.927	0.066	0.338	2019
	Breakwaters Construction	Project Site	6/1/2019	11/30/2019	extended	On-Site Crew Boat	TB	Crew Boat	Diesel	650	1	33%	100%		275357	0.492	0.537	9.843	0.373	0.820	0.149	0.163	2.988	0.113	0.249	2019
	Breakwaters Construction	Project Site	6/1/2019	11/30/2019	extended	On-Site Tugboat	TB	Tugboat-Engine	Diesel	1200	1	25%	100%		390000	0.492	0.537	9.843	0.373	0.820	0.212	0.231	4.232	0.160	0.353	2019
	Breakwaters Construction	Project Site	6/1/2019	11/30/2019	extended	On-Site Tugboat	TBG	Tugboat-Generator	Diesel	120	1	25%	100%		39000	0.166	0.179	7.457	0.201	1.268	0.007	0.008	0.321	0.009	0.054	2019
	Breakwaters Construction	Project Site	6/1/2019	11/30/2019	extended	Transport Barge Tgboat	TB	Tugboat-Engine	Diesel	1200	1	0%	0%		0	0.492	0.537	9.843	0.373	0.820	0.000	0.000	0.000	0.000	0.000	2019
	Breakwaters Construction	Project Site	6/1/2019	11/30/2019	extended	Transport Barge Tgboat	TBG	Tugboat-Generator	Diesel	120	1	0%	0%		0	0.166	0.179	7.457	0.201	1.268	0.000	0.000	0.000	0.000	0.000	2019
2b	Breakwaters Construction	Project Site	6/1/2020	10/31/2020	extended	Crane	CC	Crane Barge	Diesel	650	1	100%	100%		715000	0.013	0.013	0.995	0.071	0.363	0.010	0.010	0.784	0.056	0.286	2020
	Breakwaters Construction	Project Site	6/1/2020	10/31/2020	extended	On-Site Crew Boat	TB	Crew Boat	Diesel	650	1	33%	100%		232995	0.492	0.537	9.843	0.373	0.820	0.126	0.138	2.528	0.096	0.211	2020
	Breakwaters Construction	Project Site	6/1/2020	10/31/2020	extended	On-Site Tugboat	TB	Tugboat-Engine	Diesel	1200	1	25%	100%		330000	0.492	0.537	9.843	0.373	0.820	0.179	0.195	3.581	0.136	0.298	2020
	Breakwaters Construction	Project Site	6/1/2020	10/31/2020	extended	On-Site Tugboat	TBG	Tugboat-Generator	Diesel	120	1	25%	100%		33000	0.166	0.179	7.457	0.201	1.268	0.006	0.007	0.271	0.007	0.046	2020
	Breakwaters Construction	Project Site	6/1/2020	10/31/2020	extended	Transport Barge Tgboat	TB	Tugboat-Engine	Diesel	1200	1	0%	0%		0	0.492	0.537	9.843	0.373	0.820	0.000	0.000	0.000	0.000	0.000	2020
	Breakwaters Construction	Project Site	6/1/2020	10/31/2020	extended	Transport Barge Tgboat	TBG	Tugboat-Generator	Diesel	120	1	0%	0%		0	0.166	0.179	7.457	0.201	1.268	0.000	0.000	0.000	0.000	0.000	2020
3	Water Hub	Project Site	6/1/2019	12/31/2019	single	Drill Rig	DRI	Drill Rig	Diesel	450	1	100%	100%		547200	0.018	0.018	1.550	0.106	0.454	0.011	0.011	0.935	0.064	0.274	2019
	Water Hub	Project Site	6/1/2019	12/31/2019	single	Mobile Crane	CRA	Mobile Crane	Diesel	200	1	100%	100%		243200	0.010	0.010	0.615	0.068	0.136	0.003	0.003	0.165	0.018	0.036	2019
	Water Hub	Project Site	6/1/2019	12/31/2019	single	Asphalt Laying Eqp	ASP	Asphalt Laying Eqp	Diesel	80	1	100%	100%		97280	0.042	0.043	1.300	0.132	1.210	0.004	0.005	0.139	0.014	0.130	2019
	Water Hub	Project Site	6/1/2019	12/31/2019	single	Roller	ROL	Roller	Diesel	80	1	100%	100%		97280	0.039	0.040	1.040	0.109	1.020	0.004	0.004	0.112	0.012	0.109	2019
	Water Hub	Project Site	6/1/2019	12/31/2019	single	Generator	GEN	Generator	Diesel	100	1	100%	100%		121600	0.029	0.030	1.600	0.179	0.884	0.004	0.004	0.214	0.024	0.118	2019
3b	Water Hub	Project Site	1/1/2020	5/31/2020	single	Drill Rig	DRI	Drill Rig	Diesel	450	1	100%	100%		388800	0.018	0.018	1.550	0.106	0.454	0.008	0.008	0.664	0.045	0.195	2020
	Water Hub	Project Site	1/1/2020	5/31/2020	single	Mobile Crane	CRA	Mobile Crane	Diesel	200	1	100%	100%		172800	0.010	0.010	0.615	0.068	0.136	0.002	0.002	0.117	0.013	0.026	2020
	Water Hub	Project Site	1/1/2020	5/31/2020	single	Asphalt Laying Eqp	ASP	Asphalt Laying Eqp	Diesel	80	1	100%	100%		69120	0.042	0.043	1.300	0.132	1.210	0.003	0.003	0.099	0.010	0.092	2020
	Water Hub	Project Site	1/1/2020	5/31/2020	single	Roller	ROL	Roller	Diesel	80	1	100%	100%		69120	0.039	0.040	1.040	0.109	1.020	0.003	0.003	0.079	0.008	0.078	2020
	Water Hub	Project Site	1/1/2020	5/31/2020	single	Generator	GEN	Generator	Diesel	100	1	100%	100%		86400	0.029	0.030	1.600	0.179	0.884	0.003	0.003	0.152	0.017	0.084	2020
4	Beach Fill	Project Site	6/17/2020	7/26/2020	single	Bulldozer	BD	Bulldozer	Diesel	250	1	100%	100%		56000	0.016	0.017	0.614	0.086	0.191	0.001	0.001	0.038	0.005	0.012	2020
	Beach Fill	Project Site	6/17/2020	7/26/2020	single	Front End Loader	FEL	Front End Loader	Diesel	300	1	100%	100%		67200	0.017	0.018	0.807	0.093	0.270	0.001	0.001	0.060	0.007	0.020	2020

Crew Boat Distance 3  
Average Speed 6.4  
RT Time 0.81  
49

mi  
knots  
hr  
min

Data						
Year	Sum of PM2.5	Sum of PM10	Sum of NOx	Sum of VOC	Sum of CO	
2018	0.000		0.000	0.000	0.000	0.000
2019	0.062		0.067	1.254	0.054	0.305
2020	0.238		0.258	4.816	0.209	1.170
<b>Grand Total</b>	<b>0.299</b>		<b>0.325</b>	<b>6.070</b>	<b>0.264</b>	<b>1.475</b>

**Staten Island Breakwaters - Truck Cruise Emissions**

#	Work task	Stage	Location	Start Date	End Date	# of Workers per day	Monthly Worker Trips	# of Workers	Average		Round Trip Distance (mi)	VMT	Emission Rates (g/mi)					Emissions (ton)					Year	
									Speed (mph)	Travel Time (hr)			PM2.5	PM10	NOx	VOC	CO	PM2.5	PM10	NOx	VOC	CO		
1	Shoreline Project	Earthen Berm	Project Site	10/1/2019	12/31/2019	15		836	25	1.0112	25.28		0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.00	0.00	0.00	0.00	2019
	Shoreline Project		Project Site	1/1/2020	1/31/2020	15		291	25	1.0112	25.28		0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.00	0.00	0.00	0.00	2020
	Shoreline Project	Eco-Retvetment (between Brighton Street and Manhattan Street)	Project Site	12/1/2019	12/31/2019	15		279	25	1.0112	25.28		0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.00	0.00	0.00	0.00	2019
	Shoreline Project		Project Site	1/1/2020	2/29/2020	15		544	25	1.0112	25.28		0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.00	0.00	0.00	0.00	2020
	Shoreline Project	Hybrid Dune/Retvetment	Project Site	2/1/2020	6/30/2020	15		1355	25	1.0112	25.28		0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.00	0.00	0.00	0.00	2020
	Shoreline Project	Eco-Retvetment (between Loretto Street and Sprague Avenue)	Project Site	6/1/2020	8/31/2020	15		836	25	1.0112	25.28		0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.00	0.00	0.00	0.00	2020
	Shoreline Project	Raised Edge (Retvetment with Trail)	Project Site	7/1/2020	12/31/2020	15		1671	25	1.0112	25.28		0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.00	0.00	0.00	0.00	2020
	Shoreline Project	Transition Nodes	Project Site	6/1/2020	8/31/2020	15		836	25	1.0112	25.28		0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.00	0.00	0.00	0.00	2020
2	Breakwater Construction	Breakwater Construction	Project Site	6/1/2019	11/30/2019	11		1207	25	1.0112	25.28	30513	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.01	0.00	0.09	0.09	2019
	Breakwater Construction	Breakwater Construction	Project Site	6/1/2020	10/31/2020	11		1021	25	1.0112	25.28	25810.9	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.01	0.00	0.08	0.08	2020
3	Water Hub	Water Hub	Project Site	6/1/2019	12/31/2019	15		1924	25	1.0112	25.28	48638.7	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.01	0.00	0.15	0.15	2019
	Water Hub	Water Hub	Project Site	1/1/2020	5/31/2020	15		1367	25	1.0112	25.28	34557.8	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.01	0.00	0.11	0.11	2020
4	Beach Fill Delivery	Beach Fill Delivery	Project Site	7/1/2020	8/31/2020	6		223	25	1.0112	25.28	5637.44	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.00	0.00	0.02	0.02	2020

Emissions Rates for Auto Vehicles Traveling at 25 mph

Notes

Trucks assumed to travel at an average speed (including delays associated with congestion and red lights) of 25 mph  
Trucks origin/destination assumed to be within 1 hour travel time from project site

AVO 1.09  
Auto Share 92%

Trip Distance: 12.64

\*Source: From Transportation Energy Data Book - Edition 34, Table 8.9 (Trip Statistics by Trip Purpose)  
X:\DEPARTMENTS\Air Quality\Resources\Energy\Transportation Energy Data Book (ORNL)

Data					
Year	Sum of PM2.5	Sum of PM10	Sum of NOx	Sum of VOC	Sum of CO
2018	0.000	0.000	0.000	0.000	0.000
2019	0.062	0.067	1.254	0.054	0.305
2020	0.238	0.258	4.816	0.209	1.170
Grand Total	0.299	0.325	6.070	0.264	1.475

**Staten Island Breakwaters - Truck Cruise Emissions**

#	Work task	Stage	Location	Start Date	End Date	Truck Type	Truck Code	Daily Trucks	Total Deliveries for Period	Average Speed (mph)	Travel Time (hr)	Round Trip Distance (mi)	VMT	Emission Rates (g/mi)					Emissions (ton)					Year	
														PM2.5	PM10	NOx	VOC	CO	PM2.5	PM10	NOx	VOC	CO		
1	Shoreline Project	Earthen Berm	Project Site	10/1/2019	12/31/2019	Dump Truck	DT	3	198	25	7.344	184	0	0.56	0.61	11.30	0.49	2.75	0.00	0.00	0.00	0.00	0.00	2019	
	Shoreline Project		Project Site	1/1/2020	1/31/2020	Dump Truck	DT	3	69	25	7.344	184	0	0.56	0.61	11.30	0.49	2.75	0.00	0.00	0.00	0.00	0.00	2020	
	Shoreline Project	Eco-Revetment (between Brighton Street and Manhattan Street)	Project Site	12/1/2019	12/31/2019	Dump Truck	DT	2	44	25	7.344	184	0	0.56	0.61	11.30	0.49	2.75	0.00	0.00	0.00	0.00	0.00	2019	
	Shoreline Project		Project Site	1/1/2020	2/29/2020	Dump Truck	DT	2	86	25	7.344	184	0	0.56	0.61	11.30	0.49	2.75	0.00	0.00	0.00	0.00	0.00	2020	
	Shoreline Project	Hybrid Dune/Revetment	Project Site	2/1/2020	6/30/2020	Dump Truck	DT	15	1605	25	7.344	184	0	0.56	0.61	11.30	0.49	2.75	0.00	0.00	0.00	0.00	0.00	2020	
	Shoreline Project	Eco-Revetment (between Loretto Street and Sprague Avenue)	Project Site	6/1/2020	8/31/2020	Dump Truck	DT	7	462	25	7.344	184	0	0.56	0.61	11.30	0.49	2.75	0.00	0.00	0.00	0.00	0.00	2020	
	Shoreline Project	Raised Edge (Revetment with Trail)	Project Site	7/1/2020	12/31/2020	Dump Truck	DT	19	2508	25	7.344	184	0	0.56	0.61	11.30	0.49	2.75	0.00	0.00	0.00	0.00	0.00	2020	
	Shoreline Project	Transition Nodes	Project Site	6/1/2020	8/31/2020	Dump Truck	DT	3	198	25	7.344	184	0	0.56	0.61	11.30	0.49	2.75	0.00	0.00	0.00	0.00	0.00	2020	
	2	Breakwater Construction	Breakwater Construction	Project Site	7/16/2018	1/31/2019				0	25	7.344	184	0	0.56	0.61	11.30	0.49	2.75	0.00	0.00	0.00	0.00	0.00	2018
	3	Water Hub	Water Hub	Project Site	6/1/2019	12/31/2019	Concrete Truck	CT	2.5	380	25	0.6	15	5700	0.56	0.61	11.30	0.49	2.75	0.00	0.00	0.07	0.00	0.02	2019
Water Hub		Water Hub	Project Site	1/1/2020	5/31/2020	Concrete Truck	CT	2.5	270	25	0.6	15	4050	0.56	0.61	11.30	0.49	2.75	0.00	0.00	0.05	0.00	0.01	2020	
Water Hub		Water Hub	Project Site	6/1/2019	12/31/2019	Tractor Trailer	TT	2.5	380	25	10	250	95000	0.56	0.61	11.30	0.49	2.75	0.06	0.06	1.18	0.05	0.29	2019	
4	Water Hub	Water Hub	Project Site	1/1/2020	5/31/2020	Tractor Trailer	TT	2.5	270	25	10	250	67500	0.56	0.61	11.30	0.49	2.75	0.04	0.05	0.84	0.04	0.20	2020	
	Beach Fill Delivery	Beach Fill Delivery	Project Site	7/1/2020	8/31/2020	Dump Truck	DT	39	1716	25	7.344	184	315058	0.56	0.61	11.30	0.49	2.75	0.19	0.21	3.92	0.17	0.95	2020	

Emissions Rates for Heavy Vehicles Traveling at 25 mph

Notes

- Trucks assumed to travel at an average speed (including delays associated with congestion and red lights) of 25 mph
- Trucks origin/destination assumed to be within 1 hour travel time from project site

Data					
Year	Sum of PM2.5	Sum of PM10	Sum of NOx	Sum of VOC	Sum of CO
2018	0.000	0.000	0.000	0.000	0.000
2019	0.002	0.002	0.025	0.003	0.007
2020	0.001	0.002	0.024	0.003	0.006
Grand Total	0.003	0.003	0.049	0.005	0.013

**Staten Island Breakwaters - Construction Truck Idle Emissions**

Phase	Work task	Location	Start Date	End Date	Truck Type	Truck Code	Total Deliveries for Period	On-Site Vehicle Idle Time (hr)	Total On-Site Idle Time (hr)	Emission Rates (g/hr)					Emissions (ton)					Year
										PM2.5	PM10	NOx	VOC	CO	PM2.5	PM10	NOx	VOC	CO	
1	Shoreline Project	Project Site	10/1/2019	12/31/2019	Dump Truck	DT	198	0.05		3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2019
	Shoreline Project	Project Site	1/1/2020	1/31/2020	Dump Truck	DT	69	0.05		3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2020
	Shoreline Project	Project Site	12/1/2019	12/31/2019	Dump Truck	DT	44	0.05		3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2019
	Shoreline Project	Project Site	1/1/2020	2/29/2020	Dump Truck	DT	86	0.05		3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2020
	Shoreline Project	Project Site	2/1/2020	6/30/2020	Dump Truck	DT	1605	0.05		3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2020
	Shoreline Project	Project Site	6/1/2020	8/31/2020	Dump Truck	DT	462	0.05		3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2020
	Shoreline Project	Project Site	7/1/2020	12/31/2020	Dump Truck	DT	2508	0.05		3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2020
	Shoreline Project	Project Site	6/1/2020	8/31/2020	Dump Truck	DT	198	0.05		3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2020
2	Breakwater Construction	Project Site	7/16/2018	1/31/2019				0.05	0	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2018
3	Water Hub	Project Site	6/1/2019	12/31/2019	Concrete Truck	CT	380	1	380	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.02	0.00	0.01	2019
	Water Hub	Project Site	1/1/2020	5/31/2020	Concrete Truck	CT	270	1	270	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.02	0.00	0.00	2020
	Water Hub	Project Site	6/1/2019	12/31/2019	Tracotr Trailer	TT	380	0.05	19	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2019
	Water Hub	Project Site	1/1/2020	5/31/2020	Tracotr Trailer	TT	270	0.05	13.5	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2020
4	Beach Fill Delivery	Project Site	7/1/2020	8/31/2020	Dump Truck	DT	1716	0.05	85.8	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.01	0.00	0.00	2020

Idle Emissions Rates for Heavy Vehicles

Notes

- Concrete Trucks are assumed to idle for 1 hour per trip on site
- Dump Truck / Flat Bed Truck are assumed to idle for 3 minutes per trip on site



Data						
Year	Sum of PM2.5	Sum of PM10	Sum of NOx	Sum of CO	Sum of VOC	
2019	1.051	1.146	21.871	1.956	0.812	
2020	1.051	1.146	21.871	1.956	0.812	
<b>Grand Total</b>	<b>2.101</b>	<b>2.292</b>	<b>43.742</b>	<b>3.912</b>	<b>1.623</b>	

**Staten Island Breakwaters - Tug Boat Delivery Emissions**

Phase	Work task	Location	Start Date	End Date	Truck Type	Truck Code	Total Deliveries for Period	Round Trip Distance (mi)	VMT	Average Speed (knots)	Travel Time (hr)	Emission Rates (g/hr)					Emissions (ton)					Year
												PM2.5	PM10	NOx	VOC	CO	PM2.5	PM10	NOx	VOC	CO	
2a	Breakwaters	Project Site	6/1/2019	11/30/2019	Tug Boat/Barge	TB	115	100	11500	6.4	1561.4	610.46	665.76	12706.73	471.58	1136.45	1.05	1.15	21.87	0.81	1.96	2019
2b	Breakwaters	Project Site	6/1/2020	10/31/2020	Tug Boat/Barge	TB	115	100	11500	6.4	1561.4	610.46	665.76	12706.73	471.58	1136.45	1.05	1.15	21.87	0.81	1.96	2020
							Total		230													

Notes

Tugs assumed to travel at an average speed of 6.4 knots  
Round Trip Distance measured between site and Tilcon Quarry Sheafe Road New Hamburg, NY 12590

Total Square Footage (gsf)
8,900

**Emission Factors (lb/MMBtu)**

	PM2.5	PM10	NOx	VOC	CO	SO2
Fuel Oil	0.0075	0.0075	0.0980	0.0054	0.0824	0.0006
Natural Gas	0.0121	0.0121	0.1286	0.0178	0.0357	0.0015

2005 Energy Consumption Factor for New York:

60.3	tho Btu/yr-sqft
------	-----------------

Heating Values

Fuel Oil	140,000	Btu/gal
Natural Gas	1,020	Btu/scf

Sulfur Content	15	ppm
----------------	----	-----

	Annual Consumption	
Energy	537	MMBtu/yr
Fuel Oil	3,833	gal/yr
Natural Gas	52,615	scf/yr

**Emission (lb/yr)**

	PM2.5	PM10	NOx	VOC	CO	SO2
Fuel Oil	4.0	4.0	52.6	2.9	44.2	0.3
Natural Gas	6.5	6.5	69.0	9.6	19.2	0.8

Proposed Event/Activity	Season/Month	Frequency	Approximate Attendance	Likely Travel Method
Tree planting events	Spring/Fall	Twice per year	100-300	Auto/bus
Beach cleanups with schools, Boy Scouts, and Girl Scouts	Throughout the year	Ideally three times per week and as scheduled	Groups of 10 to 50	Auto
First day of season beach walks	Spring, Summer, Fall, and Winter	Four times per year	5-25	Auto
Earth/Arbor Day activities	April	One day or week per year	25-100	Auto/Bus
DEC citizen science Horseshoe crab monitoring	May-June	Once a year	5-15	Auto
CHP Dunes, Drawing, and Dendrology "Walk and talk"	May-September	Once per month (Sunday)	5-25	Auto
CHP Dunes, Drawing, and Dendrology EarthART	May-September	Once per month (Wednesday)	5-25	Auto
CHP Dunes, Drawing, and Dendrology "Chalk and talk"	May-September	Once per month (weekday)	5-25	Auto
CHP Dunes, Drawing, and Dendrology "Coastal Crafting"	May-September	Once per week (Saturday)	5-25	Auto
Shore birding talks and walks	Spring and Fall	Four times per year	5-25	Auto
Exhibitions	Throughout the year	Shows generally run for 4-6 weeks	XX	Auto
Greenbelt Education extension (maritime focus)	July-August (summer camp and school field trips during the school year)		Summer Camp 20-25/Field Trips - 10-15	Auto/Bus

School Bus Occupancy	17
Auto Occupancy	1.75

CEQR Table 18-7 Average One-Way Taxi Trip Lengths (Miles)				
Origin	Manhattan	Manhattan	Other NYC	Unknown Destination
	2		9	2.32
		11	6	7.88
		2.32	7.88	N/A

Annual Attendance	Annual Vehicles	
	Autos	Bus
600	343	35
7800	4,457	
100	57	
700	400	41
15	9	
300	171	
300	171	
300	171	
300	171	
100	57	
3825		225
	6,009	301
	Annual VMT	
	47,348	2,376

Conservatively includes maximum attendance utilizing both auto and bus

Conservatively includes maximum attendance utilizing both auto and bus

9 weeks (5 days per week) summer camp; 180 school days; exclusively bus

	Emission Factors (g/mi)				
	PM2.5	PM10	NOx	VOC	CO
Auto	0.008	0.009	0.250	0.066	2.758
Bus	0.442	0.481	16.127	1.018	6.011

Emissions (ton)				
0.002	0.002	0.055	0.006	0.160

Alternative 4

<b>Staten Island Breakwaters Construction Activity</b>					
<b>Annual Emissions (ton/yr)</b>					
<b>Year</b>	<b>PM2.5</b>	<b>PM10</b>	<b>NOx</b>	<b>VOC</b>	<b>CO</b>
2018	<0.1	<0.1	<0.1	<0.1	<0.1
2019	0.1	0.1	1.7	0.1	0.5
2020	1.2	1.3	26.2	1.4	7.0
2021+	0.0	0.0	0.0	0.0	0.0

Staten Island Breakwaters Non-Road Emissions Factors

Equipment Lookup	Equipment Type	Equipment Code	Details	Engine type	Size (hp)	PM2.5	PM10	NOx	VOC	CO	SO2
AC_10	Air Compresso	AC		Diesel	10	0.150	0.154	1.860	0.241	1.930	0.002
BD_250	Bulldozer	BD		Diesel	250	0.016	0.017	0.614	0.086	0.191	0.002
CC_650	ge Crawler Cr	CC	) T Crane on Ba	Diesel	650	0.013	0.013	0.995	0.071	0.363	0.002
EX_330	Excavator	EX		Diesel	350	0.015	0.016	0.832	0.086	0.331	0.002
FEL_200	ont End Load	FEL		Diesel	200	0.017	0.018	0.807	0.093	0.270	0.002
FEL_300	ont End Load	FEL		Diesel	300	0.017	0.018	0.807	0.093	0.270	0.002
GEN_100	Generator	GEN		Diesel	100	0.029	0.030	1.600	0.179	0.884	0.002
DRI_450	Drill Rig	DRI		Diesel	450	0.018	0.018	1.550	0.106	0.454	0.002
CRA_200	Mobile Crane	CRA		Diesel	200	0.010	0.010	0.615	0.068	0.136	0.002
ASP_80	phalt Laying E	ASP		Diesel	80	0.042	0.043	1.300	0.132	1.210	0.003
ROL_80	Roller	ROL		Diesel	80	0.039	0.040	1.040	0.109	1.020	0.003
GEN_100	Generator	GEN		Diesel	100	0.029	0.030	1.600	0.179	0.884	0.002
TB_650	Tug Boat	TB	40' Tug Boat	Diesel	650	0.492	0.537	9.843	0.373	0.820	0.005
TB_1200	Tug Boat	TB	40' Tug Boat	Diesel	1200	0.492	0.537	9.843	0.373	0.820	0.005
TBG_120	Tug Boat	TBG	40' Tug Boat	Diesel	120	0.166	0.179	7.457	0.201	1.268	0.005

	PM2.5	PM10	NOx	VOC	CO	SO2
Tug Boat Emis: Main Engines g/hp-hr	0.49	0.54	9.84	0.37	0.82	0.01
Aux Generator g/hp-hr	0.17	0.18	7.46	0.20	1.27	0.01
g/hr	610.46	665.76	12706.73	471.58	1136.45	6.64

Equipment Code	Size (hp)	Data					
		Max of PM2.5	Max of PM10	Max of NOx	Max of VOC	Max of CO	Max of SO2
AC	10	0.150	0.154	1.860	0.241	1.930	0.002
CC	650	0.013	0.013	0.995	0.071	0.363	0.002
TB	1200	0.492	0.537	9.843	0.373	0.820	0.005
	650	0.492	0.537	9.843	0.373	0.820	0.005
EX	350	0.015	0.016	0.832	0.086	0.331	0.002
	200	0.017	0.018	0.807	0.093	0.270	0.002
FEL	300	0.017	0.018	0.807	0.093	0.270	0.002
	100	0.029	0.030	1.600	0.179	0.884	0.002
TBG	120	0.166	0.179	7.457	0.201	1.268	0.005
BD	250	0.016	0.017	0.614	0.086	0.191	0.002
DRI	450	0.018	0.018	1.550	0.106	0.454	0.002
CRA	200	0.010	0.010	0.615	0.068	0.136	0.002
ASP	80	0.042	0.043	1.300	0.132	1.210	0.003
ROL	80	0.039	0.040	1.040	0.109	1.020	0.003

Year	Sum of CO	Sum of VOC	Sum of NOx	Sum of PM10	Sum of PM2.5
2018	0.000	0.000	0.000	0.000	0.000
2019	0.260	0.068	0.631	0.013	0.013
2020	1.530	0.405	3.658	0.079	0.077
<b>Grand Total</b>	<b>1.791</b>	<b>0.473</b>	<b>4.289</b>	<b>0.092</b>	<b>0.089</b>

single=	7 am to 3 pm
extended=	7 am to 6 pm
double =	7 am to 1 pm
	Hours
single	8
extended	10
double	16

**Staten Island Breakwaters - Anticipated Construction Schedule & Equipment Emissions**

Phase	Work task	Location	Start Date	End Date	Shift	Equipment Type	Equipment Code	Details	Engine type	Size (hp)	Quantity	Peak Daily Use	Average Use for Duration	Elevation and other Notes	Expected Annual Energy Use (hp-hr)	Emission Rates (g/hp-hr)					Emissions (ton)					Year
																PM2.5	PM10	NOx	VOC	CO	PM2.5	PM10	NOx	VOC	CO	
1a	Shoreline Construction	Project Site	10/1/2019	12/31/2019	single	Excavator	EX	Excavator	Diesel	350	2	100%	100%		369600	0.015	0.016	0.832	0.086	0.331	0.006	0.006	0.339	0.035	0.135	2019
	Shoreline Construction	Project Site	10/1/2019	12/31/2019	single	Front End Loaders	FEL	Front End Loaders	Diesel	200	2	100%	100%		211200	0.017	0.018	0.807	0.093	0.270	0.004	0.004	0.188	0.022	0.063	2019
	Shoreline Construction	Project Site	10/1/2019	12/31/2019	single	Generator	GEN	Generator	Diesel	100	1	100%	100%		52800	0.029	0.030	1.600	0.179	0.884	0.002	0.002	0.093	0.010	0.051	2019
	Shoreline Construction	Project Site	10/1/2019	12/31/2019	single	Compressor	AC	Compressor	Diesel	10	1	100%	100%		5280	0.150	0.154	1.860	0.241	1.930	0.001	0.001	0.011	0.001	0.011	2019
1b	Shoreline Construction	Project Site	1/1/2020	12/31/2020	single	Excavator	EX	Excavator	Diesel	350	2	100%	100%		1467200	0.015	0.016	0.832	0.086	0.331	0.024	0.025	1.346	0.139	0.535	2020
	Shoreline Construction	Project Site	1/1/2019	12/31/2020	single	Front End Loaders	FEL	Front End Loaders	Diesel	200	2	100%	100%		1673600	0.017	0.018	0.807	0.093	0.270	0.032	0.033	1.489	0.172	0.498	2020
	Shoreline Construction	Project Site	1/1/2019	12/31/2020	single	Generator	GEN	Generator	Diesel	100	1	100%	100%		418400	0.029	0.030	1.600	0.179	0.884	0.013	0.014	0.738	0.083	0.408	2020
	Shoreline Construction	Project Site	1/1/2019	12/31/2020	single	Compressor	AC	Compressor	Diesel	10	1	100%	100%		41840	0.150	0.154	1.860	0.241	1.930	0.007	0.007	0.086	0.011	0.089	2020
2a	Breakwaters Construction	Project Site	6/1/2019	11/30/2019	extended	Crane	CC	Crane Barge	Diesel	650	1	100%	100%			0.013	0.013	0.995	0.071	0.363	0.000	0.000	0.000	0.000	0.000	2019
	Breakwaters Construction	Project Site	6/1/2019	11/30/2019	extended	On-Site Crew Boat	TB	Crew Boat	Diesel	650	1	33%	100%			0.492	0.537	9.843	0.373	0.820	0.000	0.000	0.000	0.000	0.000	2019
	Breakwaters Construction	Project Site	6/1/2019	11/30/2019	extended	On-Site Tugboat	TB	Tugboat-Engine	Diesel	1200	1	25%	100%			0.492	0.537	9.843	0.373	0.820	0.000	0.000	0.000	0.000	0.000	2019
	Breakwaters Construction	Project Site	6/1/2019	11/30/2019	extended	On-Site Tugboat	TBG	Tugboat-Generator	Diesel	120	1	25%	100%			0.166	0.179	7.457	0.201	1.268	0.000	0.000	0.000	0.000	0.000	2019
	Breakwaters Construction	Project Site	6/1/2019	11/30/2019	extended	Transport Barge Tgboat	TB	Tugboat-Engine	Diesel	1200	1	0%	0%			0.492	0.537	9.843	0.373	0.820	0.000	0.000	0.000	0.000	0.000	2019
	Breakwaters Construction	Project Site	6/1/2019	11/30/2019	extended	Transport Barge Tgboat	TBG	Tugboat-Generator	Diesel	120	1	0%	0%			0.166	0.179	7.457	0.201	1.268	0.000	0.000	0.000	0.000	0.000	2019
2b	Breakwaters Construction	Project Site	6/1/2020	10/31/2020	extended	Crane	CC	Crane Barge	Diesel	650	1	100%	100%			0.013	0.013	0.995	0.071	0.363	0.000	0.000	0.000	0.000	0.000	2020
	Breakwaters Construction	Project Site	6/1/2020	10/31/2020	extended	On-Site Crew Boat	TB	Crew Boat	Diesel	650	1	33%	100%			0.492	0.537	9.843	0.373	0.820	0.000	0.000	0.000	0.000	0.000	2020
	Breakwaters Construction	Project Site	6/1/2020	10/31/2020	extended	On-Site Tugboat	TB	Tugboat-Engine	Diesel	1200	1	25%	100%			0.492	0.537	9.843	0.373	0.820	0.000	0.000	0.000	0.000	0.000	2020
	Breakwaters Construction	Project Site	6/1/2020	10/31/2020	extended	On-Site Tugboat	TBG	Tugboat-Generator	Diesel	120	1	25%	100%			0.166	0.179	7.457	0.201	1.268	0.000	0.000	0.000	0.000	0.000	2020
	Breakwaters Construction	Project Site	6/1/2020	10/31/2020	extended	Transport Barge Tgboat	TB	Tugboat-Engine	Diesel	1200	1	0%	0%			0.492	0.537	9.843	0.373	0.820	0.000	0.000	0.000	0.000	0.000	2020
	Breakwaters Construction	Project Site	6/1/2020	10/31/2020	extended	Transport Barge Tgboat	TBG	Tugboat-Generator	Diesel	120	1	0%	0%			0.166	0.179	7.457	0.201	1.268	0.000	0.000	0.000	0.000	0.000	2020
3a	Water Hub	Project Site	6/1/2019	12/31/2019	single	Drill Rig	DRI	Drill Rig	Diesel	450	1	100%	100%			0.018	0.018	1.550	0.106	0.454	0.000	0.000	0.000	0.000	0.000	2019
	Water Hub	Project Site	6/1/2019	12/31/2019	single	Mobile Crane	CRA	Mobile Crane	Diesel	200	1	100%	100%			0.010	0.010	0.615	0.068	0.136	0.000	0.000	0.000	0.000	0.000	2019
	Water Hub	Project Site	6/1/2019	12/31/2019	single	Asphalt Laying Eqp	ASP	Asphalt Laying Eqp	Diesel	80	1	100%	100%			0.042	0.043	1.300	0.132	1.210	0.000	0.000	0.000	0.000	0.000	2019
	Water Hub	Project Site	6/1/2019	12/31/2019	single	Roller	ROL	Roller	Diesel	80	1	100%	100%			0.039	0.040	1.040	0.109	1.020	0.000	0.000	0.000	0.000	0.000	2019
	Water Hub	Project Site	6/1/2019	12/31/2019	single	Generator	GEN	Generator	Diesel	100	1	100%	100%			0.029	0.030	1.600	0.179	0.884	0.000	0.000	0.000	0.000	0.000	2019
3b	Water Hub	Project Site	1/1/2020	5/31/2020	single	Drill Rig	DRI	Drill Rig	Diesel	450	1	100%	100%			0.018	0.018	1.550	0.106	0.454	0.000	0.000	0.000	0.000	0.000	2020
	Water Hub	Project Site	1/1/2020	5/31/2020	single	Mobile Crane	CRA	Mobile Crane	Diesel	200	1	100%	100%			0.010	0.010	0.615	0.068	0.136	0.000	0.000	0.000	0.000	0.000	2020
	Water Hub	Project Site	1/1/2020	5/31/2020	single	Asphalt Laying Eqp	ASP	Asphalt Laying Eqp	Diesel	80	1	100%	100%			0.042	0.043	1.300	0.132	1.210	0.000	0.000	0.000	0.000	0.000	2020
	Water Hub	Project Site	1/1/2020	5/31/2020	single	Roller	ROL	Roller	Diesel	80	1	100%	100%			0.039	0.040	1.040	0.109	1.020	0.000	0.000	0.000	0.000	0.000	2020
	Water Hub	Project Site	1/1/2020	5/31/2020	single	Generator	GEN	Generator	Diesel	100	1	100%	100%			0.029	0.030	1.600	0.179	0.884	0.000	0.000	0.000	0.000	0.000	2020
4	Beach Fill	Project Site	6/17/2020	7/26/2020	single	Bulldozer	BD	Bulldozer	Diesel	250	1	100%	100%			0.016	0.017	0.614	0.086	0.191	0.000	0.000	0.000	0.000	0.000	2020
	Beach Fill	Project Site	6/17/2020	7/26/2020	single	Front End Loader	FEL	Front End Loader	Diesel	300	1	100%	100%			0.017	0.018	0.807	0.093	0.270	0.000	0.000	0.000	0.000	0.000	2020

Crew Boat Distance 3 mi  
Average Speed 6.4 knots  
RT Time 0.81 hr  
49 min

		Data				
Year	Sum of PM2.5	Sum of PM10	Sum of NOx	Sum of VOC	Sum of CO	
2018	0.000		0.000	0.000	0.000	
2019	0.027		0.030	0.553	0.024	
2020	0.556		0.604	11.271	0.490	
Grand Total	0.583		0.634	11.824	0.514	

**Staten Island Breakwaters - Truck Cruise Emissions**

#	Work task	Stage	Location	Start Date	End Date	# of Workers per day	Monthly Worker Trips	# of Workers	Average		Round Trip Distance		Emission Rates (g/m)					Emissions (ton)					Year
									Speed (mph)	Travel Time (hr)	(mi)	VMT	PM2.5	PM10	NOx	VOC	CO	PM2.5	PM10	NOx	VOC	CO	
1	Shoreline Project	Earthen Berm	Project Site	10/1/2019	12/31/2019	15		836	25	1.0112	25.28	21134.1	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.01	0.00	0.06	2019
	Shoreline Project		Project Site	1/1/2020	1/31/2020	15		291	25	1.0112	25.28	7356.48	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.00	0.00	0.02	2020
	Shoreline Project	Eco-Retvetment (between Brighton Street and Manhattan Street)	Project Site	12/1/2019	12/31/2019	15		279	25	1.0112	25.28	7053.12	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.00	0.00	0.02	2019
	Shoreline Project		Project Site	1/1/2020	2/29/2020	15		544	25	1.0112	25.28	13752.3	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.00	0.00	0.04	2020
	Shoreline Project	Hybrid Dune/Retvetment	Project Site	2/1/2020	6/30/2020	15		1355	25	1.0112	25.28	34254.4	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.01	0.00	0.10	2020
	Shoreline Project	Eco-Retvetment (between Loretto Street and Sprague Avenue)	Project Site	6/1/2020	8/31/2020	15		836	25	1.0112	25.28	21134.1	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.01	0.00	0.06	2020
	Shoreline Project	Raised Edge (Retvetment with Trail)	Project Site	7/1/2020	12/31/2020	15		1671	25	1.0112	25.28	42242.9	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.01	0.00	0.13	2020
	Shoreline Project	Transition Nodes	Project Site	6/1/2020	8/31/2020	15		836	25	1.0112	25.28	21134.1	0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.01	0.00	0.06	2020
2	Breakwater Construction	Breakwater Construction	Project Site	6/1/2019	11/30/2019	11		1207	25	1.0112	25.28		0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.00	0.00	0.00	2018
	Breakwater Construction	Breakwater Construction	Project Site	6/1/2020	10/31/2020	11		1021	25	1.0112	25.28		0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.00	0.00	0.00	2020
3	Water Hub	Water Hub	Project Site	6/1/2019	12/31/2019	15		1924	25	1.0112	25.28		0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.00	0.00	0.00	2019
	Water Hub	Water Hub	Project Site	1/1/2020	5/31/2020	15		1367	25	1.0112	25.28		0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.00	0.00	0.00	2020
4	Beach Fill Delivery	Beach Fill Delivery	Project Site	7/1/2020	8/31/2020	6		223	25	1.0112	25.28		0.01	0.01	0.25	0.07	2.76	0.00	0.00	0.00	0.00	0.00	2020

Emissions Rates for Auto Vehicles Traveling at 25 mph

Notes

Trucks assumed to travel at an average speed (including delays associated with congestion and red lights) of 25 mph  
Trucks origin/destination assumed to be within 1 hour travel time from project site

AVO 1.09  
Auto Share 92%

Trip Distance: 12.64

\*Source: From Transportation Energy Data Book - Edition 34, Table 8.9 (Trip Statistics by Trip Purpose)  
X:\DEPARTMENTS\Air Quality\Resources\Energy\Transportation Energy Data Book (ORNL)

Year	Data				
	Sum of PM2.5	Sum of PM10	Sum of NOx	Sum of VOC	Sum of CO
2018	0.000		0.000	0.000	0.000
2019	0.027		0.030	0.553	0.024
2020	0.556		0.604	11.271	0.490
Grand Total	0.583		0.634	11.824	0.514

**Staten Island Breakwaters - Truck Cruise Emissions**

#	Work task	Stage	Location	Start Date	End Date	Truck Type	Truck Code	Daily Trucks	Total Deliveries for Period	Average Speed (mph)	Travel Time (hr)	Round Trip Distance (mi)	VMT	Emission Rates (g/mi)					Emissions (ton)					Year
														PM2.5	PM10	NOx	VOC	CO	PM2.5	PM10	NOx	VOC	CO	
1	Shoreline Project	Earthen Berm	Project Site	10/1/2019	12/31/2019	Dump Truck	DT	3	198	25	7.344	184	36352.8	0.56	0.61	11.30	0.49	2.75	0.02	0.02	0.45	0.02	0.11	2019
	Shoreline Project					Dump Truck	DT	3	69	25	7.344	184	12668.4	0.56	0.61	11.30	0.49	2.75	0.01	0.01	0.16	0.01	0.04	0.04
	Shoreline Project	Eco-Revetment (between Brighton Street and Manhattan Street)	Project Site	12/1/2019	12/31/2019	Dump Truck	DT	2	44	25	7.344	184	8078.4	0.56	0.61	11.30	0.49	2.75	0.00	0.01	0.10	0.00	0.02	2019
	Shoreline Project					Dump Truck	DT	2	86	25	7.344	184	15789.6	0.56	0.61	11.30	0.49	2.75	0.01	0.01	0.20	0.01	0.05	0.05
	Shoreline Project	Hybrid Dune/Revetment	Project Site	2/1/2020	8/30/2020	Dump Truck	DT	15	1605	25	7.344	184	29467.8	0.56	0.61	11.30	0.49	2.75	0.18	0.20	3.67	0.16	0.89	2020
	Shoreline Project					Dump Truck	DT	7	462	25	7.344	184	84823.2	0.56	0.61	11.30	0.49	2.75	0.05	0.06	1.06	0.05	0.26	2020
	Shoreline Project	Eco-Revetment (between Loretto Street and Sprague Avenue)	Project Site	6/1/2020	8/31/2020	Dump Truck	DT	7	462	25	7.344	184	84823.2	0.56	0.61	11.30	0.49	2.75	0.05	0.06	1.06	0.05	0.26	2020
	Shoreline Project					Dump Truck	DT	19	2508	25	7.344	184	460469	0.56	0.61	11.30	0.49	2.75	0.28	0.31	5.74	0.25	1.39	2020
	Shoreline Project	Raised Edge (Revetment with Trail)	Project Site	7/1/2020	12/31/2020	Dump Truck	DT	19	2508	25	7.344	184	460469	0.56	0.61	11.30	0.49	2.75	0.28	0.31	5.74	0.25	1.39	2020
	Shoreline Project					Dump Truck	DT	3	198	25	7.344	184	36352.8	0.56	0.61	11.30	0.49	2.75	0.02	0.02	0.45	0.02	0.11	2020
2	Breakwater Construction	Breakwater Construction	Project Site	7/16/2018	1/31/2019				0	25	7.344	184		0.56	0.61	11.30	0.49	2.75	0.00	0.00	0.00	0.00	0.00	2018
3	Water Hub	Water Hub	Project Site	6/1/2019	12/31/2019	Concrete Truck	CT	2.5	380	25	0.6	15		0.56	0.61	11.30	0.49	2.75	0.00	0.00	0.00	0.00	0.00	2019
						Concrete Truck	CT	2.5	270	25	0.6	15		0.56	0.61	11.30	0.49	2.75	0.00	0.00	0.00	0.00	0.00	2020
	Water Hub	Water Hub	Project Site	6/1/2019	12/31/2019	Tractor Trailer	TT	2.5	380	25	10	250		0.56	0.61	11.30	0.49	2.75	0.00	0.00	0.00	0.00	0.00	2019
						Tractor Trailer	TT	2.5	270	25	10	250		0.56	0.61	11.30	0.49	2.75	0.00	0.00	0.00	0.00	0.00	2020
4	Beach Fill Delivery	Beach Fill Delivery	Project Site	7/1/2020	8/31/2020	Dump Truck	DT	39	1716	25	7.344	184		0.56	0.61	11.30	0.49	2.75	0.00	0.00	0.00	0.00	0.00	2020

Emissions Rates for Heavy Vehicles Traveling at 25 mph

**Notes**

- Trucks assumed to travel at an average speed (including delays associated with congestion and red lights) of 25 mph
- Trucks origin/destination assumed to be within 1 hour travel time from project site



Data					
Year	Sum of PM2.5	Sum of PM10	Sum of NOx	Sum of VOC	Sum of CO
2018	0.000	0.000	0.000	0.000	0.000
2019	0.000	0.000	0.001	0.000	0.000
2020	0.001	0.001	0.016	0.002	0.004
<b>Grand Total</b>	<b>0.001</b>	<b>0.001</b>	<b>0.017</b>	<b>0.002</b>	<b>0.005</b>

**Staten Island Breakwaters - Construction Truck Idle Emissions**

Phase	Work task	Location	Start Date	End Date	Truck Type	Truck Code	Total Deliveries for Period	On-Site Vehicle Idle Time (hr)	Total On-Site Idle Time (hr)	Emission Rates (g/hr)					Emissions (ton)					Year
										PM2.5	PM10	NOx	VOC	CO	PM2.5	PM10	NOx	VOC	CO	
1	Shoreline Project	Project Site	10/1/2019	12/31/2019	Dump Truck	DT	198	0.05	9.9	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2019
	Shoreline Project	Project Site	1/1/2020	1/31/2020	Dump Truck	DT	69	0.05	3.45	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2020
	Shoreline Project	Project Site	12/1/2019	12/31/2019	Dump Truck	DT	44	0.05	2.2	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2019
	Shoreline Project	Project Site	1/1/2020	2/29/2020	Dump Truck	DT	86	0.05	4.3	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2020
	Shoreline Project	Project Site	2/1/2020	6/30/2020	Dump Truck	DT	1605	0.05	80.25	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.01	0.00	0.00	2020
	Shoreline Project	Project Site	6/1/2020	8/31/2020	Dump Truck	DT	462	0.05	23.1	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2020
	Shoreline Project	Project Site	7/1/2020	12/31/2020	Dump Truck	DT	2508	0.05	125.4	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.01	0.00	0.00	2020
	Shoreline Project	Project Site	6/1/2020	8/31/2020	Dump Truck	DT	198	0.05	9.9	3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2020
	2	Breakwater Construction	Project Site	7/16/2018	1/31/2019				0.05		3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00
3	Water Hub	Project Site	6/1/2019	12/31/2019	Concrete Truck	CT	380	1		3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2019
	Water Hub	Project Site	1/1/2020	5/31/2020	Concrete Truck	CT	270	1		3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2020
	Water Hub	Project Site	6/1/2019	12/31/2019	Tracotr Trailer	TT	380	0.05		3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2019
	Water Hub	Project Site	1/1/2020	5/31/2020	Tracotr Trailer	TT	270	0.05		3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2020
4	Beach Fill Delivery	Project Site	7/1/2020	8/31/2020	Dump Truck	DT	1716	0.05		3.55	3.86	57.91	6.20	15.91	0.00	0.00	0.00	0.00	0.00	2020

Idle Emissions Rates for Heavy Vehicles

Notes

- Concrete Trucks are assumed to idle for 1 hour per trip on site
- Dump Truck / Flat Bed Truck are assumed to idle for 3 minutes per trip on site

Data					
Year	Sum of PM2.5	Sum of PM10	Sum of NOx	Sum of CO	Sum of VOC
2019	0.000	0.000	0.000	0.000	0.000
2020	0.000	0.000	0.000	0.000	0.000
<b>Grand Total</b>	<b>0.000</b>	<b>0.000</b>	<b>0.000</b>	<b>0.000</b>	<b>0.000</b>

**Staten Island Breakwaters - Tug Boat Delivery Emissions**

Phase	Work task	Location	Start Date	End Date	Truck Type	Truck Code	Total Deliveries for Period	Round Trip Distance (mi)	VMT	Average Speed (knots)	Travel Time (hr)	Emission Rates (g/hr)					Emissions (ton)					Year
												PM2.5	PM10	NOx	VOC	CO	PM2.5	PM10	NOx	VOC	CO	
2a	Breakwaters	Project Site	6/1/2019	11/30/2019	Tug Boat/Barge	TB	115	100		6.4	0.0	610.46	665.76	12706.73	471.58	1136.45	0.00	0.00	0.00	0.00	0.00	2019
2b	Breakwaters	Project Site	6/1/2020	10/31/2020	Tug Boat/Barge	TB	115	100		6.4	0.0	610.46	665.76	12706.73	471.58	1136.45	0.00	0.00	0.00	0.00	0.00	2020
							Total	230														

Notes

Tugs assumed to travel at an average speed of 6.4 knots  
Round Trip Distance measured between site and Tilcon Quarry Sheafe Road New Hamburg, NY 12590

Total Square Footage (gsf)
8,900

2005 Energy Consumption Factor for New York:

60.3	tho Btu/yr-sqft
------	-----------------

Heating Values

Fuel Oil	140,000	Btu/gal
Natural Gas	1,020	Btu/scf

Sulfur Content	15 ppm
----------------	--------

	Annual Consumption	
Energy	537	MMBtu/yr
Fuel Oil	3,833	gal/yr
Natural Gas	52,615	scf/yr

**Emission Factors (lb/MMBtu)**

	PM2.5	PM10	NOx	VOC	CO	SO2
Fuel Oil	0.0075	0.0075	0.0980	0.0054	0.0824	0.0006
Natural Gas	0.0121	0.0121	0.1286	0.0178	0.0357	0.0015

**Emission (lb/yr)**

	PM2.5	PM10	NOx	VOC	CO	SO2
Fuel Oil						
Natural Gas						

Proposed Event/Activity	Season/Month	Frequency	Approximate Attendance	Likely Travel Method
Tree planting events	Spring/Fall	Twice per year	100-300	Auto/bus
Beach cleanups with schools, Boy Scouts, and Girl Scouts	Throughout the year	Ideally three times per week and as scheduled	Groups of 10 to 50	Auto
First day of season beach walks	Spring, Summer, Fall, and Winter	Four times per year	5-25	Auto
Earth/Arbor Day activities	April	One day or week per year	25-100	Auto/Bus
DEC citizen science Horseshoe crab monitoring	May-June	Once a year	5-15	Auto
CHP Dunes, Drawing, and Dendrology "Walk and talk"	May-September	Once per month (Sunday)	5-25	Auto
CHP Dunes, Drawing, and Dendrology EarthART	May-September	Once per month (Wednesday)	5-25	Auto
CHP Dunes, Drawing, and Dendrology "Chalk and talk"	May-September	Once per month (weekday)	5-25	Auto
CHP Dunes, Drawing, and Dendrology "Coastal Crafting"	May-September	Once per week (Saturday)	5-25	Auto
Shore birding talks and walks	Spring and Fall	Four times per year	5-25	Auto
Exhibitions	Throughout the year	Shows generally run for 4-6 weeks	XX	Auto
Greenbelt Education extension (maritime focus)	July-August (summer camp and school field trips during the school year)		Summer Camp 20-25/Field Trips - 10-15	Auto/Bus

School Bus Occupancy	17
Auto Occupancy	1.75

CEQR Table 18-7 Average One-Way Taxi Trip Lengths (Miles)				
Origin	Manhattan	Manhattan	Other NYC	Unknown Destination
	2		9	2.32
		11	6	7.88
		2.32	7.88	N/A

Annual Attendance	Annual Vehicles	
	Autos	Bus
600	343	35
7800	4,457	
100	57	
700	400	41
15	9	
300	171	
300	171	
300	171	
300	171	
100	57	
3825		225
	6,009	301
	Annual VMT	
	47,348	2,376

Conservatively includes maximum attendance utilizing both auto and bus

Conservatively includes maximum attendance utilizing both auto and bus

9 weeks (5 days per week) summer camp; 180 school days; exclusively bus

	Emission Factors (g/mi)				
	PM2.5	PM10	NOx	VOC	CO
Auto	0.008	0.009	0.250	0.066	2.758
Bus	0.442	0.481	16.127	1.018	6.011

Emissions (ton)				